



Circular Letter No.: 2016.130

Issue Date: 11 January 2016

Application: BEAM Plus NB Version 1.1
BEAM Plus NB Version 1.2

Effective Date: ALL BEAM Plus submissions after 25 January 2016


Water Use (WU)

For the BEAM Plus Final Assessment, the Applicant shall demonstrate that the Plumbing System is complete, including but not limited to the following:

- 1) Declaration of compliance with the governing utility requirements including but not limited to the Waterworks Ordinance, Plumbing Regulations, Water Services Application Procedure and Circular Letters.
- 2) All government utility water meters and sub meters where fitted, are installed and operational.
- 3) All water storage tanks are installed, filled and operational.
- 4) All water fixtures shall be documented, installed and shall comply with the governing utility regulations, including but not limited to:
 - i. All faucets/ taps for washbasin, kitchen sinks, bathroom sinks and janitor sinks;
 - ii. All shower valves, shower heads and rain showers;
 - iii. All flow controllers/ flow limiters;
 - iv. All isolation valves, stop cocks and pressure reducing valves.
- 5) The plumbing system has been inspected and disinfected before the building is occupied.
- 6) All 'As-Built' plumbing schematic and layout drawings are provided.

Note: The governing utility in Hong Kong SAR shall be Water Supplies Department (WSD).

Signed: _____


Sr. Kenneth CHAN Jor Kin
Vice Chairperson of Technical Review Committee